

**Name of Work: Renovation & Modification of cupboard (10 nos) work at Old T-VI B-2/1 at NIT Silchar.**

Completion period: 30 days.

OR:  
CR:  
OM:

**Schedule of Rate**

<b>Sl. No.</b>	<b>Description of Item</b>	<b>Unit</b>	<b>Quantity</b>
1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and below	each	10.00
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	Sqm	60.00
3	Distempering with 1st quality acrylic washable distemper (ready made) of approved manufacturer and of required shade and colour complete. as per manufacturer's specification. One or more coats on old work	Sqm	20.00
4	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface. Water thinnable cement primer	Sqm	20.00
5	15 mm cement plaster on rough side of single or half brick wall of mix : 1:4 (1 cement: 4 coarse sand)	Sqm	20.00
6	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, panelling and dash fasteners to be paid for separately) : Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15	Kg	120

<b>Sl. No.</b>	<b>Description of Item</b>	<b>Unit</b>	<b>Quantity</b>
7	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 4.00 mm thickness	Sqm	20.00
8	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete : 100 x 10mm	each	38.00
9	Providing and fixing chromium plated brass night latch of approved quality including necessary screws etc. complete.	each	20.00
10	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS:15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm	60.00

Total Estimated Cost: Rs. 1,97,793.00 over DSR 2016 with 55.88% cost Index.

<b>Quoted Rate in percentage (%) over estimated cost (In word &amp; fig)</b>	
--	--