

Schedule of Rate

Name of work: Replacement of roofing Sheet at Mechanical Building & New Class room Building at NIT Silchar

Completion period: 30 days.

OR:
CR:
OM:

Sl. No.	Description of Item	Unit	Quantity	Rate in word	Rate in figure	Amount
1	Dismantling roofing including ridges, hips, valleys and gutters etc.,and stacking the material within 50 metres lead of:	Sqm	310.00			
2	Providing & fixing UV stabilised fiberglass reinforced plastic sheetroofing up to any pitch, including fixing with polymer coated 'J' or 'L'hooks, bolts & nuts 8mm dia. G.Iplain/bitumen washers completebut excluding the cost of purlins, rafters, trusses etc. The sheetsshall be manufactured out 2400 TEX panel rovigs in corporating minimum 0.3% ultra-violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conformto IS 10192 and IS 12866.The sheets shall be opaque or translucent,clear or pigmented, textured or smooth as specified. 2 mm thick corrugated (2.5" or 4.2" or 6") or step-down(2" or 3" or 6") as specified.	Sqm	310.00			
3	Providing and fixing precoated galvanised steelsheetroofingaccessories 0.50 mm (+ 0.05 %) total coated thickness, Zinc coating120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete :Ridges plain (500 - 600mm)	Rm	50.00			

Total = Rs.